

SMRID's Bow Island Lateral 26 project

**Case study – Owner's perspective
72" diameter Weholite pipe installation**

June 2nd, 2010
Irrigation Technical Conference

Engineering and project management

Myles Kasun (MPE) design and project manager

Steve Nixon (MPE) resident inspector

David Joachim (SMRID) project coordinator


Pipe Supply

- KWH Pipe (manufactured in Saskatoon)

INSTALLATION

- BYZ Construction (Prime contractor)

ST. MARY RIVER IRRIGATION DISTRICT



BACKGROUND

1998 report

Report 1998 (MPE)

- Envisioned construction of a 3.3 km self-leveling, lined canal
- ~ 40 km of downstream PVC pipeline.

Total project Acres = 9,162

Identified 258 seepage affected acres

Image © 2010 DigitalGlobe

© 2010 Google

Imagery Dates: Aug 3, 2006 - Aug 4, 2006

49°56'38.15" N 111°14'36.04" W elev 813 m

Eye alt 2.72 km



Issues

- Maintenance of the 3.3 km self leveling canal (algae, aquatic weeds)
- Cost of earthworks for embankment construction and liner

2007 / 2008

- Construction was postponed over 10 years due to other district priorities
- With larger diameter PVC and poly pipe now available, pipe option was re-examined
- Buried pipeline was favored over the canal option; found to be an economic alternative.

Weholite Pipe option

- Flowrate = 117 cfs ($3.3 \text{ m}^3/\text{s}$) at start
- 72" (1800 mm) diameter had a large enough cross sectional area to allow for single pipe.

Phase 1 Project Components


PHASE 1:


- Lined settling pond (125 m long) + cast in place inlet structure
- 1.6 km of 72" diameter (1800 mm) poly 'Weholite' pipe
- Cast-in-place concrete junction box

Subsequent phases

- ~ 40 + km PVC pipe ranging in size from 4" to 48" diameter

Phase 1: Weholite Pipe






**Cover of 1 - 2.5 m
(still required cuts 3 - 4.5 m due to
large pipe diameter)**

Pipe Characteristics

- Profile walled pipe
- RSC (Ring Stiffness coefficient) 160
- 15 psi rating was used (max 30 psi available for Weholite)
- 50' (15 m) lengths

Installation



BACKFILL DETAIL
1:50

Pipe Joining

- Joining done by a mobile extruder inside the pipe by KWH Ltd
- Averaged 2-3 pipe lengths joined per day

Installation photos

- Photos courtesy Steve Nixon, MPE

Lead hoe





Portable extrusion machine











20/11/2008


**Mobile extruder
powered by onsite
generator (supplied
by KWH)**



Banding
removed



21/11/2008



Further 'welding' done on the outside of the pipe after the steel banding was removed (hand held extruder)

26 / 11 / 2008



Granular used
throughout

24/11/2008



Granular for haunching/bedding

- 15,864 tonnes of granular
- Cost >\$300 grand

Tee constructed onsite (1800 by 300 tee)











19/01/2009



Elbows

- No thrust blocks were used
- Constructed by KWH's shop in Saskatoon



Conditions









Installation issues

- Wet
- Constant pumping in trench during installation was required
- Pipe installation took longer than foreseen, there were stoppages due to weather (November to early Feb.)
- *Installation took a long time*

Installation issues

- No problems with excess dirt creating a 'hump' over pipeline as the land was gently rolling and it was possible to feather out the material

Discussion items

- Cost of pipe supply was competitive
- Installation was slow; expensive
- Cost of future installation bids ???

Before



After





Before

Image © 2010 DigitalGlobe

© 2010 Google

552 m
Imagery Dates: Aug 3, 2006 - Aug 4, 2006

49°56'38.15" N 111°14'36.04" W elev 813 m

Eye alt 2.72 km



After



Conclusions

- **System commissioned in May 2009**
- **Water supervisor: “Increased capacity”.**
- **Seepage has been reduced through the section, arable land reclaimed (boon to adjacent landowners).**
- **SMRID is overall satisfied with final product**

Kudos

- MPE, KWH, BYZ